



WBS 6.1.3

Pixel Communication & Services

K.K. Gan
Level-3 Manager & CAM
The Ohio State University

U.S. ATLAS HL-LHC Upgrade Project DOE CD-1 Director's Review
Brookhaven National Laboratory
Upton, NY
May 7-9, 2018



Outline

- Technical Details
 - Deliverable Overview
 - R&D Status and Plans
- Project Management
 - Management Structure: CAM and ICs
 - Cost and Schedule Estimating Methodology
 - ES&H
- Cost and Schedule
 - Budget and Schedule estimates
 - Risk and Uncertainty
- Closing Remarks




Technical Details



Deliverable Overview

Provide communications and services to
US deliverable:
Inner Pixel System



CQ.2



WBS 6.1.3.1

CQ.2

- Institution: Oklahoma State
- 6.1.3.1: Flex Circuit
 - design/prototype/production of flex circuits for transmission of command/clock, LV, HV, DCS (safety monitors)
 - Challenge: high-speed transmission/low signal loss or voltage drop with minimum material
 - Technical Specs (see later)

	Production	Pre-Production
Flexes needed for inner system	300	
Yield	72%	
Flexes to be produced	420	30
Total material cost	\$245,000	\$35,000



WBS 6.1.3.2

CQ.2

- Institution: SLAC
- 6.1.3.2: Patch Panel 0 (PP0)
 - Design/prototype/production of PP0 with connectors for data, command/clock, LV, HV, DCS (safety monitors)
 - challenge: minimum material and insertion loss in bandwidth/signal strength



PP0 type	Quantity	Components	PCB fab	Assembly	Total
Data Barrel L0	96	\$120	\$14	\$20	\$14,784
Data Barrel L1	120	\$100	\$14	\$20	\$16,080
Data Endcap	648	\$80	\$14	\$20	\$73,872
SP chains	264	\$100	\$14	\$20	\$35,376
Total					\$140,112
Yield					85%
Total inc. yield					\$164,838



WBS 6.1.3.3

CQ.2

- Institution: SLAC
- 6.1.3.3: TwinAx
 - Twin co-axial cables
 - Need 864 bundles of four TwinAx cables
 - Opto-box : soldering to mini-PCB with connector
 - PP0: soldering to PP0 for inner detector and to mini-PCB at outer detector
 - Challenge: high-speed data transmission up to 5.5 m of skinny cables with acceptable attenuation
- Technical Specs (see later)





WBS 6.1.3.4

CQ.2

- Institution: UC Santa Cruz
- 6.1.3.4: Type-1 bundle
 - design/prototype/production of cable bundles for command/clock, LV, HV, DCS (safety monitors)
 - Challenge: compact bundles with connectorization of minimum loss
 - Technical Specs (see later)



WBS 6.1.3.5

CQ.2

- Institution: Ohio State
- 6.1.3.5: Optical Carrier Board
 - QA of optical carry boards designed by Bern
 - Production of 280 boards, including 80% yield
- Technical Specs (see later)



WBS 6.1.3.6

CQ.2

- Institution: Oklahoma State
- 6.1.3.6: Serial Power Supply
 - design/prototype/production of power supplies, backplane, control system, chassis, Type-II cables
 - Challenge: supply constant current up to 16 FE ASICs in series
 - Technical Specs: supplies of constant current of 8 A per channel to the front-end chips with a voltage range of 1.2-1.5 V per chip

Description	Production	Pre-production
Pixel Modules in the pixel inner system	2456	
Pixel Modules per power supply	8	
Power supplies to be installed	307	
Production yield	90%	
Power supplies to be produced	341	31



WBS 6.1.3.6

CQ.2

Description	Quantity
Cables needed in the pixel inner system	142
Production yield	90%
Cables to be produced	158



WBS 6.1.3.7

CQ.2

- Institution: Southern Methodist U.
- 6.1.3.7: Equalizer ASIC
 - design/prototype/production of equalizer ASIC
 - Challenge: correct for degradation of high frequency component of the data signal after propagation through TwinAx
 - Technical Specs: (see later)



Technical Specs

CQ.2

- 6.1.3.1 (Type-0 Services), 6.1.3.2 (Patch Panel 0), 6.1.3.3 (Twinax Cables), 6.1.3.4 (Type-I Services) and 6.1.3.7 (Equalizer): radiation-hard data transmission from the modules to the optical converters at 5.12 Gb/s up to 5.5 meters with maximum attenuation of 20 dB.
- 6.1.3.5 (Opto-Links): optical converters for converting electrical data signals to optical signals for transmission to the DAQ system at 5.12 Gb/s per channel and vice versa for the clock/command signal at 160 Mb/s from the DAQ system.
- 6.1.3.6 (Serial Powering): Serial power supplies produce a constant current up to 8 A per serial power chain and provide a voltage of 1.5-2.0 V per module, with a maximum of 16 modules per chain.



R&D

CQ.4

- 6.1.3.1:
 - Identified flex stack-up and materials. Preliminary layout completed. Production in FY20.
- 6.1.3.2:
 - PP0: Initial conceptual design completed. Production in FY21.
- 6.1.3.3
 - TwinAx: cables of different dielectric material and gauges prototyped. Currently evaluating a possible final prototype 30 AWG cable with much smaller cross section due to much reduced wire spacing. Production in FY20.
- 6.1.3.4:
 - Study cross talk and breakdown voltage on Type-I cable bundle. Production in FY20.
- 6.1.3.6:
 - Tested serial powering with several FE-I4 chips. Production in FY23.
- 6.1.3.7:
 - Design of equalizer circuit and clock recovery circuit started. Production in FY20




Project Management



L3 Project

CQ.5





L3 Project

CQ.5

- 6.1.3.1+6.1.3.6: flex circuit and power supply
 - Oklahoma State: F. Rizatdinova leads the effort with S. Welch as the lead engineer at cost.
 - Cost estimate mostly based on quotes and data from previous hardware development projects
- 6.1.3.2+6.1.3.3: PP0/TwinAx
 - SLAC: Su Dong leads the effort with contributions from physicists plus engineers and technicians available at cost.
 - TwinAX cost estimate based on several years of R&D and PP0 based on fabricating similar objects for Insertable Barrel Layer (IBL) of ATLAS Pixel detector



L3 Project

CQ.5

- **6.1.3.4: Type-I bundle**
 - UCSC: J. Nielson leads the effort with contributions from physicists plus engineers and technicians at cost.
 - Cost estimate based on similar objects for Insertable Barrel Layer (IBL) of ATLAS Pixel detector
- **6.1.3.5: Opto carrier board**
 - Ohio State: K.K. Gan leads the effort with contributions from physicists plus engineers and technicians at cost.
 - Cost estimate based on building two generations of opto-boards for the Pixel detector of ATLAS
- **6.1.3.7: Equalizer**
 - SMU: J. Ye leads the effort with contributions from engineers and technicians at cost.
 - Cost estimate based on design/prototyping of other ASICs



ES&H

CQ.6

- Safety is of the highest priority within the Project
 - Work at each institute adheres strictly to its ES&H policies

Institute	Institute ES&H Contact
Ohio State	M. St. Clair (https://ehs.osu.edu)
Oklahoma State	K. Southworth (https://ehs.okstate.edu)
SLAC	C. Fried (http://www-group.slac.stanford.edu/esh/)
SMU	B. Chance (https://www.smu.edu/BusinessFinance/RiskManagement/Health-Safety)
UC Santa Cruz	L. Wisser (https://ehs.ucsc.edu)

- The BNL ES&H Liaison provides oversight and advice
 - US ATLAS HL-LHC Institute Contacts act as interfaces between their institute and BNL and CERN
- Main Hazards for this Deliverable
 - Radiation: CERN test beams are in controlled areas
 - All work done in compliance with safety policies at the institute or CERN




Cost and Schedule




Budget & Effort

CQ.4

Total Cost by Resource Category



Labor, Material and Travel (%)





Schedule

CQ.3

- Items needed at SLAC integration in 2022:
 - 6.1.3.1: flex circuits
 - 6.1.3.2: PPO
 - 6.1.3.3: TwinAx
 - 6.1.2.4: Type-I bundles
- Items needed at CERN in 2024:
 - 6.1.3.5: opto carrier boards
 - 6.1.3.6: serial power supplies
 - 6.1.3.7: equalizer
- Main external dependencies:
 - System test: data aggregator ASIC + cables + opto-links for operation at 5.12 Gb/s



Risk and Uncertainty

CQ.3

- **RD-06-01-03-001: 5 Gb/s data transmission speed not achievable**
 - Response: use slightly larger twinax cables or double the number of data cables to operate at 2.56 G/s, and/or operate at lower bandwidth and make use of data compression.
 - Mitigation: allocate more resource in connectorization
 - Cost: \$9K-\$12K
 - Delay: 2-4 months
- **RD-06-01-03-002: Serial powering fails to meet specifications**
 - Response: allocate more resource for prototyping and use new cables instead of the existing cables.
 - Mitigation: More prototyping of power supply and study of the cooling requirement
 - Cost: \$70K-\$120K
 - Delay: 2-4 months



Milestones

CQ.3

- FY19: Flex FDR
- FY19: TwinAx FDR
- FY19: Type-1 bundle FDR
- FY20: Flex PRR
- FY20: TwinAx PRR
- FY20: Type-1 bundle PRR
- FY21: PP0 FDR
- FY21: PP0 PRR
- FY22: power supply PDR
- FY23: power supply PRR



Closing Remarks

- Communication and Services WBS contains both active and passive deliverables
- Some R&D are well advanced and others just started
- Main technical challenge:
 - Achieve 5.12 Gb/s data transmission at up to 5.5 m of cables plus connectors with less than 20 dB of attenuation



BACKUP



Bio Sketch of L3 Manager

- K.K. Gan, Professor of Physics, The Ohio State University
- Member of ATLAS since 1998
- Leading the design and fabrication of two generations of optical links for the ATLAS pixel detector




Institute Capabilities

- 6.1.3.1, 6.1.3.6, Oklahoma State:
 - Good facility for electronics development and fabrication
 - One engineer available at cost
 - Previously involved in the Insertable B-Layer pixel project
- 6.1.3.2, 6.1.3.3, SLAC:
 - Large facility for electronics development and fabrication
 - Large pool of engineers and technician available at cost
 - Previously involved in the Insertable B-Layer pixel project
- 6.1.3.4, UC Santa Cruz:
 - Good facility for electronics development and fabrication
 - Pool of engineers and technician available at cost
 - Previously involved in the Insertable B-Layer pixel project
- 6.1.3.5, Ohio State:
 - Clean room with automatic wire bonders and probe stations etc
 - Two engineers available at cost
 - Previously leading two ATLAS pixel opto-link projects
- 6.1.3.7, Southern Methodist:
 - Good facility for optical electronics development
 - Engineers available at cost
 - Previously leading ATLAS LAr opto-link projects




Budget & Effort

WBS 6.01.03.01 OKS Chart - L3 Ttl Cost by Res Category




WBS 6.01.03.01 OKS Chart - L3 Lbr Mat and Trvl (%)






Budget & Effort

WBS 6.01.03.02 SLAC Chart - L3 Ttl Cost by Res Category



	FY18	FY19	FY20	FY21	FY22
ENG	11,659	18,764	37,106	238,279	99,445
MAT		5,932	6,110	109,502	19,447
TECH	2,980	5,430	9,484	18,034	15,480
TRAVD		3,324			
TRAVF				4,418	


WBS 6.01.03.02 SLAC Chart-L3 Lbr Mat and Trvl (%)






Budget & Effort

WBS 6.01.03.03 SLAC Chart - L3 Ttl Cost by Res Category



	BCWS					
ENG	46,640	36,030	14,844	15,926		
MAT	3,998	11,034	25,417	1,259	495,143	3,947
TECH	6,371	30,102	4,377	4,508		157
TRAVD		12,467				


WBS 6.01.03.03 SLAC Chart - L3 Lbr Mat and Trvl (%)






Budget & Effort

WBS 6.01.03.04 UCSC Chart - L3 Ttl Cost by Res Category




WBS 6.01.03.04 UCSC Chart - L3 Lbr Mat and Trvl (%)






Budget & Effort

WBS 6.01.03.05 OSU Chart - L3 Ttl Cost by Res Category




WBS 6.01.03.05 OSU Chart-L3 Lbr Mat and Trvl (%)






Budget & Effort

WBS 6.01.03.06 OKS Chart - L3 Ttl Cost by Res Category



	BCWS							
ENG	67,713	74,113	116,335	86,460	238,854	282,241	101,666	43,397
EQUIP					13,912	33,435	233,681	
MAT	6,842	80,433	34,810	53,332	122,544	41,784	46,498	15,373
TRAVD	3,003	9,281	6,373	6,564	12,152	12,187		
TRAVF	13,516	18,562	19,118	19,692	28,734	29,872	5,380	4,374


WBS 6.01.03.06 OKS Chart-L3 Lbr Mat and Trvl (%)





Budget & Effort

WBS 6.01.03.07 SMU Chart - L3 Ttl Cost by Res Category



WBS 6.01.03.07 SMU Chart-L3 Lbr Mat and Trvl (%)

